174R-102827 REV.: 2 DESCRIPTION REV. DATE BY - 3/8 x 1 1/2 RUBBER GASKET SCREW DOWN EVERY 2 FEET UNIT OVERHANG 0 20 GAGE UPPER FLASHING SHIPPED LOOSE AND FIELD INSTALLED - RUBBER GASKET TO ENCLOSE ENTIRE OUTSIDE OF CURB. - 3/8 TYP. AIR GAP SHIPPED LOOSE AND FIELD INSTALLED 3/8 SHIPPING SPACER (REMOVED DURING INSIDE CURB ---INSTALLATION) 20 GAGE LOWER FLASHING SHIPPED LOOSE AND FIELD INSTALLED TO WOOD NAILER 21 1/8 0 2 X 2 (1.5 X 1.5) CCA40 TREATED WOOD NAILER ALL AROUND CURB 0 2" THICK INSULATION BOARD B.O. WATER PROOF MEMBRANE B.O. 0 OPTIONAL CANT STRIP B.O. ROOF ROOF **SECTION VIEW A-A** NOTE: 1. B.O. = BY OTHERS NOT BY THE VMC GROUP OTHER MATERIALS, COMPOUNDS, OR FINISHES WITH EQUAL OR SUPERIOR PROPERTIES MAY BE SUBSTITUTED AS THEY BECOME AVAILABLE. **CERTIFIED FOR:** NONE JOB NAME: \_ MODEL TELECURB ISOLATED SHEET: NON- SEISMIC OR WIND RESTRAINT CUSTOMER: **CURB ATTACHMENT DETAIL SECTIONS** THE VMC GROUP DRAWING NO. REVISION CUSTOMER P.O.:

SALES ORDER:

The Power of Together Bloomingdale, NJ 07403

Houston, TX 77041